



Department of Civil Engineering

राष्ट्रीय प्रौद्योगिकी संस्थान कलिकट

National Institute of Technology Calicut

एन.आई.टी. कैंपस (पी.ओ.), कलिकट, केरल-673 601, भारत • NIT Campus (P.O.), Calicut, Kerala-673 601, India

Phone:
Office 0495 2286201;
Head 0495 2286200
Fax: 0495 2287250
e-mail: (HOD)
civilhod@nitc.ac.in
website: www.nitc.ac.

CED/TEST/SM/ TZV/2016030 dated 17.01.2016

02.02.2016

Your Ref. No. dtd. 17.01.2016

Professor & Head,
Dept. of Civil Engg.

To

Astron Reinforced Concrete Spacers
Labour Colony Road
Thammanam
Cochin -32

Sir,

With reference to your letter cited above, the following tests have been completed as per the relevant Indian Standard Specification and results are furnished herewith.

Test Report

- (A) Sample : Three samples of concrete spacers brought by the party.
(B) Sample identification : Given in the table below.
(C) Tests : Compressive strength test.
(D) Test results:

ASTRON A 60

Sl. No	Mark	Date of Testing	Load at failure (kN)
1	60	20.1.16	38.7
2	60	20.1.16	39.1
3	60	20.1.16	41.2
Average			39.10

The Test Charges vide our Receipt No. R-C2/15/N015/10519 dtd 20.01.2016 has already been paid. Please find the Bill of Charges enclosed here with.

Kindly acknowledge the receipt of this.

Thanking you,

Yours faithfully,

Professor & Head,
Dept. of Civil Engg.